



Be free to organize your enclosure

XL³ 400 self-assembly cabinets and enclosures, IP 43 metal or insulated



MAIN BENEFITS

- Optimised transport and stocking thanks to flat packaging
- Optimised use of space inside enclosures thanks to external cable sleeve that can be equipped with DPX³ MCCBs
- Takes: DIN rail equipment, DPX³, DPX-IS and Vistop ≤ 400 A

XL³ 400 cabinets & enclosures p. 204

Equipment selection for XL³ 400

Device	Fixing	Position	Type of device	Fixing device	Fixing plate	Faceplate for devices		
						Height (mm)	Metal	
FIXING ON DIN-RAIL								
Modular devices < 63 A	Cabinet or enclosure	vertical		0 202 06 0 202 01	-	150	0 203 00	
	Cable sleeve	vertical		0 202 03	-	150	0 203 03	
Modular devices > 63 A	Cabinet or enclosure	vertical		0 202 06 0 202 01	-	200	0 203 01	
	Cable sleeve	vertical		0 202 03	-	200	0 203 04	
Vistop 63 to 160 A	Cabinet or enclosure	vertical		0 202 06 0 202 01	-	200	0 203 01	
DPX-IS 250	Cabinet or enclosure	vertical	with modular devices	0 202 06	0 262 09	300	0 203 10	
FIXING ON PLATE								
DPX ³ 160 (Combination possible with DPX ³ 250)	Cabinet or enclosure	vertical	with or without e.l.c.bs and without direct rotary handle	-	0 202 11 + 4 210 71/73 ¹	300	0 203 10	
			with or without e.l.c.bs and with direct rotary handle	-	0 202 11 + 4 210 68	300	0 203 10	
		direct rotary handle ⁽¹⁾	-	0 202 09	300	0 203 09		
		manual supply inverter ⁽²⁾	-	0 202 11 + 4 210 58	300	0 203 10		
	horizontal	with or without e.l.c.b	-	0 202 13	150	0 203 13		
	Cable sleeve	vertical	with or without e.l.c.b	-	0 202 17	300	0 203 18	
DPX ³ 250 (Combination possible with DPX ³ 160)	Cabinet or enclosure	vertical	with or without e.l.c.b and without side motor-driven handle	-	0 202 11 + 4 210 72/74 ¹	300	0 203 10	
			with or without e.l.c.b and with side motor-driven handle	-	0 202 11 + 4 210 69	300	0 203 10	
		direct rotary handle ⁽¹⁾	-	0 202 09	300	0 203 09		
		manual supply inverter ⁽²⁾	-	0 202 11 + 4 210 58	300	0 203 10		
	horizontal	with or without e.l.c.bs	-	0 202 15	200	0 203 17		
	Cable sleeve	vertical	with or without e.l.c.bs	-	0 202 17	300	0 203 18	
DPX-IS 250	Cabinet or enclosure	vertical	device only in central position		0 202 05	300	0 203 10	
	Cable sleeve	vertical	device only		0 202 17 + 0 262 39	300	0 203 18	
DPX ³ 630	Cabinet or enclosure	vertical	device only centred		0 202 21	400	0 203 21	
			centred with e.l.c.bs		0 202 23	600	0 203 23	
	horizontal	without downstream e.l.c.bs		0 202 25	300	0 203 25		
	Cable sleeve	vertical	device only		0 202 28	400	0 203 28	
			with downstream e.l.c.bs		0 202 29	800	0 203 29	
DPX-IS 630	Cabinet or enclosure	vertical	device only		0 202 07	400	0 203 07	

1: Cat.Nos 4 210 73/74 for DPX³ with electronic earth leakage module

OPTIMISED DISTRIBUTION HX³/VX³



Full offer of optimised distribution available on request.
Download the product guide on
www.docexport.legrand.com