



# Fully adaptable enclosures

XL<sup>3</sup> 800 extendable cabinets and enclosures, 24 & 36 modules per row



XL<sup>3</sup> 800 cabinets & enclosures p. 212-213

### DISCOVER THE RANGE

- Extendable: 24 and 36 modules per row
- Two indexes of protection:
  - IP 43 up to 800 A, supplied flat with functional uprights
  - IP 55 up to 600 A, supplied without side panels
- Takes: DIN rail equipment, DPX<sup>3</sup>, DPX-IS and Vistop ≤ 800 A

### FROM IEC 60439 TO IEC 61439



XL<sup>3</sup> configurable assemblies guide to migration from IEC 60439 to IEC 61439  
 Download the guide on [www.docexport.legrand.com](http://www.docexport.legrand.com)

### Equipment selection for XL<sup>3</sup> 800

Device	Fixing	Position	Type of device	Fixing device	Fixing plate	Height (mm)	Faceplate for device		
							1/4 turn	Screw	
XL <sup>3</sup> 800 - 24 modules			XL <sup>3</sup> 800 - 24 modules						
<b>FIXING ON DIN-RAIL</b>									
Modular devices < 63 A	Cabinet or enclosure	vertical		0 206 01	-	150	0 208 00	0 209 00	
Modular devices > 63 A	Cabinet or enclosure	vertical		0 206 01	-	200	0 208 01	0 209 01	
Vistop 63 to 160 A	Cabinet or enclosure	vertical		0 206 01	-	200	0 208 01	0 209 01	
DPX-IS 250	Cabinet or enclosure	vertical	with modular devices	0 206 01	0 262 39	300	0 208 10	0 209 10	
<b>FIXING ON PLATE</b>									
DPX <sup>3</sup> 160 (combination possible with DPX <sup>3</sup> 250)	Cabinet or enclosure	vertical	without side motor-driven handle	-	0 206 11 + 4 210 71/73 <sup>(1)</sup>	300	0 208 10	0 209 10	
			with side motor-driven handle	-	0 206 11 + 4 210 68	300	0 208 10	0 209 10	
			direct rotary handle	-	0 206 08 + 4 210 71/73 <sup>(1)</sup>	300	0 208 05	0 209 05	
			manual supply inverter	-	0 206 11 + 4 210 58	300	0 208 10	0 209 10	
			motor-driven supply inverter	-	0 206 13 + 4 210 58	300	0 208 10	0 209 10	
DPX <sup>3</sup> 250 and DPX <sup>3</sup> 160-125 electronic (combination possible with DPX <sup>3</sup> 160)	Cabinet or enclosure	vertical	with or without e.l.c.bs	-	0 206 15	150	0 208 13	0 209 13	
			without side motor-driven handle	-	0 206 11 + 4 210 72/74 <sup>(1)</sup>	300	0 208 10 <sup>(2)</sup>	0 209 10	
			with side motor-driven handle	-	0 206 11 + 4 210 69	300	0 208 10 <sup>(2)</sup>	0 209 10	
			direct rotary handle	-	0 206 08 + 4 210 72/74 <sup>(1)</sup>	300	0 208 05	0 209 05	
			manual supply inverter	-	0 206 11 + 4 210 58	300	0 208 10 <sup>(2)</sup>	0 209 10	
DPX-IS 250	Cabinet or enclosure	vertical	motor-driven supply inverter	-	0 206 13 + 4 210 58	300	0 208 10 <sup>(2)</sup>	0 209 10	
			with or without e.l.c.bs	-	0 206 17	200	0 208 17	0 209 17	
			device only in central position	-	0 206 05	300	0 208 10	0 209 10	
			1 or 2 devices	-	0 206 05	300	0 208 06	0 209 06	
			DPX <sup>3</sup> 630	Cabinet or enclosure	vertical	1 to 3 devices, no e.l.c.bs	-	0 206 20	400
DPX-IS 630	Cabinet or enclosure	vertical	1 to 3 devices, with e.l.c.bs	-	0 206 22	600	0 208 22	0 209 22	
			with or without e.l.c.bs	-	0 206 23	300	0 208 23	0 209 23	
DPX-IS 1600	Cabinet or enclosure	vertical	device only	-	0 206 07	300	0 208 07	0 209 07	
			Cable sleeve	-	0 206 27	1550/1950	-	0 204 41/42	
DPX <sup>3</sup> 1600	Cabinet or enclosure	vertical	device only	-	0 211 00	300	-	0 211 13	
			horizontal	device only	-	0 211 00	400	0 211 10	0 211 11
XL <sup>3</sup> 800 - 36 modules			XL <sup>3</sup> 800 - 36 modules						
<b>FIXING ON DIN-RAIL</b>									
Modular devices < 63 A	Cabinet or enclosure	vertical		0 206 51	-	150	-	0 209 50	
Modular devices > 63 A	Cabinet or enclosure	vertical		0 206 51	-	200	-	0 209 51	
Vistop 63 to 160 A	Cabinet or enclosure	vertical		0 206 51	-	200	-	0 209 51	
DPX-IS 250	Cabinet or enclosure	vertical	with modular devices	0 206 51	0 262 39	300	-	0 209 60	
<b>FIXING ON PLATE</b>									
DPX <sup>3</sup> 160 (combination possible with DPX <sup>3</sup> 250)	Cabinet or enclosure	vertical	without side motor-driven handle	-	0 206 61 + 4 210 71/73 <sup>(1)</sup>	300	-	0 209 60	
			with side motor-driven handle	-	0 206 61 + 4 210 68	300	-	0 209 60	
			manual supply inverter	-	0 206 61 + 4 210 58	300	-	0 209 60	
DPX <sup>3</sup> 250 (combination possible with DPX <sup>3</sup> 160)	Cabinet or enclosure	vertical	without side motor-driven handle	-	0 206 61 + 4 210 72/74 <sup>(1)</sup>	300	-	0 209 60	
			with side motor-driven handle	-	0 206 61 + 4 210 69	300	-	0 209 60	
			manual supply inverter	-	0 206 61 + 4 210 58	300	-	0 209 60	
DPX-IS 250	Cabinet or enclosure	vertical	1 or 2 devices	-	0 206 55	300	-	0 209 60	
DPX <sup>3</sup> 630	Cabinet or enclosure	vertical	no e.l.c.bs	-	0 206 70	400	-	0 209 70	
			with e.l.c.bs	-	0 206 72	600	-	0 209 72	
DPX-IS 630	Cabinet or enclosure	vertical	device only	-	0 206 57	300	-	0 209 57	
DPX <sup>3</sup> 1600	Cabinet or enclosure	vertical	device only	-	0 211 02	400	-	0 211 12	
			horizontal	device only	-	0 211 02	400	-	0 209 84

1: Cat.Nos 4 210 73/74 for DPX<sup>3</sup> with electronic earth leakage module  
 2: Faceplate supplied